

Bill of Quantities					
SI No	Description	Unit	Quantity	Rate	Amount
A	Chokhang Maintenance				
1	Surface preparation removing by scrapping, sand papering, including scratch repairs with puty- Dry oil bound distemper.	Sq.m	234.34		
2	Providing and applying one coat of primer (Decoprime wall primer water diluted from Asian Paints or equivalent) as per painting instruction of product.	Sq.m	234.34		
3	Providing and applying two finishing coats (Apcolite Advanced emulsion water diluted from Asian Paints or equivalent) as per painting instruction of product.	Sq.m	234.34		
4	Providing and fixing anodised aluminium section for partition framing of specified sections including all the accessories such as U-rubber gasket for fixing the glass panes, weather strips or weather seals, roller, spring etc complete.	Kg	37.61		
5	Providing and fixing anodised aluminium section for doors of specified sections including all the accessories such as U-rubber gasket for fixing the glass panes, hinges 100mm (3nos), weather strips or weather seals, roller, spring etc complete.	Kg	8.82		
6	Providing and fixing plain glass pane 4mm thick on aluminium sec	Sq.m	0.92		
7	Providing and fixing of 10mm thick prelaminate particle board with necessary nails or screw etc complete.	Sq.m	16.73		
8	Providing and fixing automatic door closer (Hardwyn Grace-91) and door lock system with three nos of key.	Nos	1.00		
	Total Amount				
B	General Store Maintenance				
1	Demolishing reinforced cement concrete, including stacking steel bars and disposal of rubbish within 50m lead	Cum	0.95		



2	Removal of Aluminium partition (aluminium frames, glass, particle board and fixtures complete) including stacking of useful materials and disposal of rubbish within 50m lead.	Sq.m	10.8		
3	Removal and re-fixing of Aluminium partition including all aluminium frames, glass, particle board and fixtures complete	Sq.m	16.8		
4	Removal of steel collapsible gate including guide rails and all fixtures complete	Sq.m	7.2		
5	Providing and laying in position reinforced cement concrete work in walls (any thickness) including attached pilasters buttresses, piers, abutments etc. upto floor five level including cost of centering and shuttering -1:2:4	Cum	1.22		
6	Providing and fixing thermo mechanically treated reinforcement bar (yield strength 500mpa) for R.C.C work including cutting, bending, binding and placing in position complete.	Kg	113.12		
7	Providing and fixing white/ colored glazed tiles in flooring, treads of steps and landings laid on bed of 12mm thick cement mortar 1:3 finished with flush pointing in white cement -for 300x300mm. (including counter vertical wall)	Sq.m	139.70		
8	Providing and fixing anodised aluminium section for doors of specified sections including all the accessories such as U-rubber gasket for fixing the glass panes, hinges 100mm (3nos), weather strips or weather seals, roller, spring etc complete.	Kg	8.82		
9	Providing and fixing plain glass pane 4mm thick on aluminium section	Sq.m	1.00		
10	Providing and fixing of 10mm thick pre-laminated particle board with necessary nails or screw etc complete.	Sq.m	1.00		
11	Providing and fixing automatic door closer (Hardwyn Grace-91) and door lock system with three nos of key.	Nos	1		
12	Surface preparation removing by scrapping, sand papering, including scratch repairs with putty- Dry oil bound distemper.	Sq.m	357.70		

